

Procurement Office
Harford Community College
401 Thomas Run Road
Bel Air Maryland 21015
443.412.2307

IFB 21B-003 ARENA EXTERIOR STAIRS REPLACEMENT

ADDENDUM NO. 1

The following shall be incorporated into the captioned solicitation as though included in the original documents issued:

Questions/Answers

Q1 Drawing C-03 Handrail and concrete detail shows for cheek wall depth to be minimum of 12". Do we need to extend to the frost line?

A1 Yes for the cheek walls, see revised drawing provided.

Q2 Drawing C-03 Post detail calls from SCH-40 sleeve. Please confirm that core drilling for the hand rails posts is an acceptable option.

A2 Yes

Q3 Please provide specifications on required concrete sealer.

A3 Specifications included on revised drawing.

Q4 Please provide reinforcing requirements for concrete walls.

A4 Details on revised drawing,

Q5 Shall the steps be tied/dowelled into the adjacent walls? If required, please provide detail for tie-ins.

A5 No

END ADDENDUM 1

April 29, 2021